

PRODUCT EXPERIENCE CONCEPT · V1.4

Suq Insights

Clarity for every market day.

A comprehensive landing-page, dashboard, visual-system, content, conversion, and implementation blueprint for the production SaaS.

LANDING PAGE

**Trust →
understanding →
action**

PRODUCT

**Messy records →
useful answers**

EXPERIENCE

**Calm, credible,
merchant-first**

Updated 5 September 2026 · Canonical product source: SDLC.md v3.0 · English master copy with Spanish and French localization requirements

Document purpose and status

This document defines a coherent experience for the Suq Insights marketing site and authenticated merchant product. It turns the product behavior in `SDLC.md` into a visual direction, page narrative, dashboard structure, component inventory, responsive behavior, content system, marketing initiatives, and implementation checklist.

It is a concept and delivery brief, not a replacement for the SDLC. Where the two conflict, `SDLC.md` wins. Headlines and sample values are working copy until product, legal, localization, and evidence reviews approve them. Testimonials, customer logos, performance claims, prices, and regional availability must never be invented to fill a layout.

Outcomes this document should create

- A visitor understands the product in one screen: Suq accepts the records a merchant already has and turns them into daily sales, stock, and customer answers.
- The landing page and product feel like one brand, not a marketing theme bolted onto a generic admin template.
- The first authenticated screen is useful with real merchant data and instructive before data exists.
- Designers and engineers can make small decisions consistently: spacing, pagination, empty states, widget errors, chart colors, mobile reordering, copy tone, and conversion tracking are specified.
- Launch scope stays honest. Profit, margin, cash-flow, returns, and advertising-attribution metrics are not shown until their semantic roles and calculations exist in the product contract.

Working product promise

Know what's selling. See what runs out next. See who comes back.

Supporting promise:

Upload the records you already keep—spreadsheets, exports, pasted tables, PDFs, or photos. Suq Insights helps you confirm what they mean, then turns them into a clear daily view of your business.

This promise is specific enough to remember, broad enough for the launch catalog, and faithful to the platform's core differentiator: it adapts to merchant data instead of demanding a predefined schema.

Contents

1. Experience strategy
2. Inspiration translated into Suq
3. Brand theme: Market Day Intelligence
4. Voice, message, and copy system
5. Landing-page architecture
6. Landing-page product mockups
7. Marketing and growth initiatives
8. Authenticated product information architecture
9. Dashboard concept
10. Launch widget presentation
11. Critical supporting screens
12. Component behavior in detail
13. Responsive behavior
14. Accessibility specification
15. Localization and international UX
16. Motion and interaction
17. Analytics and measurement plan
18. Implementation architecture for the experience
19. Delivery sequence
20. Acceptance checklist
21. SDLC traceability
22. Content and design dependencies

The final pages contain source references and document ownership. Each numbered chapter begins on a new PDF page for scanning and review.

1. Experience strategy

1.1 The problem in the merchant's language

The user is not shopping for “a composable analytics substrate.” They are trying to answer practical questions before opening, ordering stock, or closing the day:

- What sold today, this week, or this month?
- Which items are moving and which are sitting?
- What will run out soon?
- Which customers returned?
- Is today's dashboard based on current, correctly interpreted data?

Their evidence is fragmented and imperfect: POS exports, marketplace files, manually maintained sheets, pasted rows, photographs of paper, and records entered while connectivity is weak. Most analytics products begin by asking them to clean, rename, map, or integrate. Suq begins by understanding what arrived, showing its reasoning, and asking the merchant to confirm only what cannot be proven.

1.2 Positioning

Category: merchant intelligence and operational analytics.

Primary differentiator: useful analysis from the records a merchant already keeps, with visible interpretation and merchant confirmation before commitment.

Emotional benefit: confidence. The merchant should feel “I know what happened, I know what needs attention, and I can see why the system believes it.”

Functional benefit: one daily view across sales velocity, inventory, retention, alerts, channels, and record freshness.

Positioning line:

Suq Insights is the daily intelligence workspace for merchants whose data does not arrive in a perfect shape.

1.3 Audience hierarchy

Audience	Immediate anxiety	Desired first proof	Primary action
Merchant owner	"I have data, but no reliable daily picture."	A recognizable upload becomes one concrete insight.	Start free / try a sample
Merchant staff	"I need to record and check today without breaking anything."	Quick entry, clear status, safe correction, and visible sync.	Enter data / review alerts
Evaluating operator	"Will this work with my strange export?"	Supported-source examples and the inference-review experience.	Explore the demo
Premium prospect	"Will the paid plan remove real limits?"	Exact contextual unlock: longer history, SMS/email alerts, sync API, team seats, multiple dashboards, exports, no ads.	Compare plans
Advertiser	"Can I reach merchants in a relevant, measurable context?"	Clearly separated advertiser proposition and audited campaign controls.	Visit advertiser portal

The primary landing page serves merchant owners. Advertiser and administrator experiences must not leak into the merchant narrative or navigation.

1.4 North-star experience

Messy in. Clear out. Nothing silently guessed.

Every important interaction should reinforce one of four qualities:

1. **Clear:** plain language, visible hierarchy, one primary action per region.
2. **Trustworthy:** interpretation evidence, data freshness, provenance, and honest unavailable states.
3. **Useful today:** insights and next actions appear before configuration options.
4. **Adaptable:** merchant-defined channels, editable models, movable widgets, multiple input forms, and localized conventions.

1.5 Experience principles

Answers before features

Lead with "what is selling?" rather than "advanced analytics." Widget titles are questions or direct outcomes, and landing-page sections describe decisions merchants can make.

Evidence beside conclusions

An insight links to the contributing widget, filtered records, or derived-state provenance. Confidence is described in plain language and supported visually; color alone never communicates certainty.

Progressive complexity

The default canvas is excellent without editing. Advanced controls—render switching, thresholds, field roles, dashboard templates—appear at the point of need.

Recovery is a first-class path

Uploads can be corrected, loads can be reversed, entries can roll back, models can be revised, and failed widgets can retry independently. The interface explains what will happen before destructive changes.

International by construction

Layouts tolerate long French labels, Spanish accents, variable currency formats, day-first dates, and locale-specific number separators. No country flag is used as a language icon.

2. Inspiration translated into Suq

The references inform different parts of Suq: Milestone supplies the theme, the ecommerce dashboard supplies product organization, and Lightdash supplies the presentation rhythm. Each is rebuilt around Suq's product behavior.

2.1 Milestone landing-page influence

Reference: [Milestone Webflow template](#)

Patterns worth carrying forward:

- Oversized, high-contrast hero typography; the updated presentation pairs left-aligned copy with a working record-review example in an open layout.
- A bold sans-serif paired with a selective italic serif for warmth and emphasis.
- Mostly white surfaces with acid-lime actions and soft mint, aqua, and lavender ambient gradients.
- An oversized product mockup that makes the software tangible immediately. Suq uses the straight-on composition specified in §3.7.
- Alternation between airy white sections and black editorial panels.
- Rounded cards, simple line illustrations, sparse hand-drawn marks, and concise feature copy.
- Product-led calls to action repeated at natural decision points.

Suq adaptation:

- Replace finance language with daily merchant decisions.
- Show a trustworthy dashboard and mapping-review sequence, not banking cards or transactions.
- Use market-inspired details abstractly—grid, rhythm, labels, tally marks—not literal bazaars, flags, or regional stereotypes.
- Keep decorative gradients outside data visualizations. Analytical colors retain stable meanings.

2.2 Ecommerce dashboard influence

Reference: [E-commerce Management Dashboard by Vetrick Wilsen for Yow](#)

Patterns worth carrying forward:

- A quiet gray application background with a large white workspace.
- A persistent left rail, top breadcrumb/context line, and clearly separated content canvas.
- Large rounded cards with restrained borders and generous internal spacing.
- Top-row metrics for quick scanning; charts and ranked lists below.
- Black or near-black primary data marks, muted secondary data, and one controlled accent.
- Clear workspace or store identity near the page title.

Suq adaptation:

- The sidebar reflects Suq’s flat merchant information architecture, not store-management modules.
- Cards become movable, resizable widget frames with explicit widget-level controls.
- “Sales by country,” order-fulfillment, and team contact panels become insight, inventory, alerts, data freshness, and top-item widgets.
- The date in the header becomes a merchant-timezone date range with freshness status.
- The product must work with incomplete capabilities: a missing customer identifier explains why retention is unavailable instead of showing zero.

2.3 Product-market references

Reference	Useful lesson	Suq’s interpretation
Triple Whale	Strong outcome language and product screenshots make an abstract data platform feel actionable.	Speak in merchant decisions and show the real daily canvas; avoid claiming AI actions or attribution features Suq does not ship.
Polar Analytics	Goal-based navigation and a no-signup demo reduce evaluation risk.	Organize use cases around selling, stock, and returning customers; provide a sample-data playground.
Milestone	Editorial contrast makes finance software feel approachable.	Use a confident black/white/lime identity with soft supporting color.
Yow dashboard shot	Spatial calm and familiar ecommerce patterns lower learning cost.	Retain the calm shell while making every analytical frame a true Suq widget instance.
Lightdash on Saaspo	A bounded page, large product demonstrations, and varied section density connect benefits to evidence.	Keep the Suq theme; present merchant questions, answers, supporting records, and a useful next action.

2.4 What not to copy

- Decorative charts that do not match a real metric contract.
- Low-contrast gray text, tiny labels, or icon-only actions without names.
- Empty customer-logo walls, fictional testimonials, or unsupported performance percentages.
- Huge animations that delay comprehension or violate reduced-motion preferences.
- A permanent right rail that reduces the twelve-column canvas or breaks small laptops.
- A fixed dashboard that visually resembles widgets but cannot actually be rearranged.
- Generic “AI-powered growth” language. Suq’s trust comes from showing interpretation, evidence, and confirmed roles.

2.5 Lightdash presentation influence

Reference: [Lightdash landing-page capture on Saaspo](#). This is a presentation reference, not a source of Suq product capabilities. Some media panels in the capture are blank; no behavior is inferred from those panels.

- **Open composition:** use shared alignment and generous gutters within the 1,280 px content maximum. The merchant review on the hero's right balances the headline on its left. Do not use outer border rails, dotted page backgrounds, or a small receipt decoration in otherwise unused hero space. These treatments were rejected in the visual review. Surface contrast, soft elevation, and rounded product containers provide separation; borders remain available for form fields, data tables, and accessible states.
- **Large product demonstration:** begin with a merchant question, a concise answer, and useful actions before the detailed dashboard. Metric buttons change the chart; a time slider changes the inspected observation; a table presents the same values; selecting a stock item changes its risk detail. The review link moves focus to the corresponding section. All controls work by keyboard and touch.
- **Feature chapters:** give records, interpretation review, and daily decisions room for one dominant mockup each. A source selector or workflow tabs change only their own stage. Mobile and reduced-motion views show readable static workflow cards.
- **Merchant situations:** use illustrative questions about incompatible exports, late numbers, and ambiguous columns in the problem section. Label them as illustrations; never give them fabricated customer identities, logos, or testimonial attribution.
- **Outcome grid:** show six inspectable principles: evidence, confirmation, source preservation, honest missing data, period context, and localization. Prefer statements demonstrated by the preview. Future behavior remains part of the delivery plan until implemented.
- **Transformation:** the existing Add → Confirm → See sequence is the first transformation timeline. Later iterations can extend it to repeated daily use; do not invent a five-day onboarding or productivity promise.
- **Closing invitation:** a dark Ink panel with lime action invites the visitor into Mercado Norte's fictional demo. The account-access alternative remains explicitly a preview until authentication is connected.
- **Brand detail:** product content carries the lime/mint palette: selected metrics, a confirmed field, and a restrained chart fill. A soft mint backdrop may sit behind the hero review panel. Do not reintroduce the decorative receipt, purple pixel artwork, copied copy, logos, security badges, or developer positioning.

The presentation revision covers the existing foundations and understanding sequence, its outcome summary, and closing invitation. Dedicated daily-question panels, the full trust demonstration, channels, offline entry, and composable dashboards remain subsequent delivery work. This revision does not mark Phase 3 or the SaaS complete.

2.6 Dropdown direction

User-supplied reference: [Profile Dropdown Menu – Clean UI Component by Mahamud Hassan Jibon](#).

The requested direction is a polished, coherent dropdown family across the application, starting on the landing page. The reference artwork could not be retrieved during implementation, so this is a Suq interpretation, not a verified reproduction: floating white panels, generous rounded rows,

compact contextual headings, muted supporting text, and an unmistakable selected check. Keep Suq's Paper, Ink, Mint, and Forest tokens; do not adopt an unrelated palette or invent a signed-in profile for public pages. The reusable behavior and acceptance contract is §12.13.

3. Brand theme: Market Day Intelligence

3.1 Theme statement

Market Day Intelligence combines the energy of a busy market with the order of a well-kept ledger. The interface feels bright, alert, and human without becoming playful about money or data integrity.

The landing page is expressive: oversized type, editorial emphasis, ambient color, and cinematic product mockups. The application is calmer: neutral surfaces, compact typography, stable semantic colors, and restrained motion. They share the same tokens, border language, icon style, and lime action color.

3.2 Visual personality

Attribute	We want	We avoid
Confidence	Strong type, direct copy, visible evidence	Hype, exaggerated claims, aggressive urgency
Warmth	Editorial serif moments, gentle color haze, human examples	Cartoon mascots in serious workflows
Clarity	Strong grouping, meaningful whitespace, labels beside icons	Glassmorphism, excessive blur, ornament around tables
Energy	Acid-lime action, crisp charts, live-status pulse	Rainbow dashboards and constant movement
Global relevance	Neutral merchant examples and flexible locale patterns	Flags, clichés, or one-market assumptions

3.3 Color system

Token	Hex	Role	Usage rule
Ink 950	#10110E	Primary text, dark panels, chart series 1	Use as the dominant high-contrast anchor.
Paper 50	#FBFBF7	Marketing background, light app surface	Warmer than pure white; do not use behind white cards without a boundary.
White	#FFFFFF	Cards, modal surfaces, dashboard canvas	Pair with a border or shadow on Paper/Mist.
Mist 100	#F0F2EC	App background, selected rows, disabled wells	Never use for essential low-contrast text.
Slate 600	#596158	Secondary copy	Minimum size 14 px; verify contrast on every surface.
Lime 400	#C9F54A	Primary action, focus emphasis, brand moment	Black text only. Never use lime text on white.
Mint 300	#9BE5C1	Healthy/complete supporting fill	Pair with Ink text and an icon or label.
Aqua 300	#9EDFED	Informational/supporting series	Not a link color on white without a darker tone.
Lavender 300	#CFC6FF	Comparison/context supporting fill	Decorative or secondary series; not error/status.
Amber 400	#F2BE4A	Warning, needs review, low confidence	Always pair with “Review” or warning icon.
Coral 500	#E9685A	Error, critical stock, destructive action	Use sparingly and with explicit text.
Forest 700	#286448	Accessible success text and positive delta	Use on pale mint or white.
Blue 700	#245E78	Accessible links and informational text	Underline body-copy links.

Semantic color is stable across marketing and product. Green means healthy or complete, amber means attention, coral means failure or urgency, and blue means informational. Positive revenue movement may use Forest, but negative values never rely on red alone: arrows, signs, and labels remain visible.

Dark mode is a post-launch enhancement unless scheduled by the implementation plan. Tokens should be named semantically so it can be added without rewriting components; launch testing should not be diluted by shipping an unvalidated second theme.

3.4 Typography

Primary sans: Inter Variable or a metrically compatible system sans. Use for navigation, product UI, body copy, tables, controls, and chart labels.

Editorial serif: Source Serif 4 Italic. Use selectively in landing-page headlines, quotations, and one-line moments of emphasis. Do not use in tables, form labels, or dense dashboard cards.

Style	Desktop	Mobile	Weight/line height	Use
Display XL	72 px	44 px	650 / 0.98	Landing hero only
Display L	56 px	38 px	650 / 1.02	Major campaign page hero
H1 product	32 px	28 px	650 / 1.18	Screen title
H2 section	40 px	30 px	620 / 1.12	Marketing section heading
H2 product	22 px	20 px	650 / 1.25	Product region heading
Body L	20 px	18 px	400 / 1.55	Marketing deck
Body	16 px	16 px	400 / 1.55	Default copy
UI	14 px	14 px	500 / 1.4	Controls and card content
Data L	30 px	26 px	650, tabular / 1.1	KPI values
Caption	12 px	12 px	550 / 1.35	Metadata; never essential alone

Use tabular numerals for metrics. Never tighten tracking on translated uppercase labels; use sentence case in product UI.

3.5 Layout, spacing, radius, and elevation

- Base spacing unit: 4 px.
- Common steps: 4, 8, 12, 16, 20, 24, 32, 40, 56, 72, 96, 128.
- Marketing content maximum: 1,280 px; readable copy maximum: 680 px.
- Dashboard maximum: fluid within viewport; content padding 24 px desktop, 16 px tablet/mobile.
- Dashboard grid: twelve columns desktop, eight tablet, four mobile. Widget gap: 16 px compact, 20 px standard.
- Radius: 8 px controls, 12 px small cards, 16 px widgets, 24 px marketing feature panels, pill only for tags/status.
- Borders: 1 px #D9DDD2 ; selected border: 2 px Ink or accessible Forest.
- Shadows are subtle and functional: cards use border first; overlays use 0 16px 48px rgba(16,17,14,.16) .
- Minimum interactive target: 44 × 44 px, even when the visible icon is 20 px.

3.6 Iconography and illustration

- Use a single 1.75 px rounded line-icon family, 20 px default and 16 px in dense tables.
- Pair unfamiliar icons with visible labels. Tooltips supplement; they never replace accessible names.
- Use hand-drawn marks only on marketing pages: a short underline, star, arrow, or tally. They should feel like annotations in a merchant's notebook, not decorative noise.
- Empty-state illustrations are abstract tables, columns, receipts, boxes, and trend marks. Avoid region-specific costumes, currency piles, or literal marketplace scenes.

3.7 Product mockup style

Mockups are the connective tissue between landing page and product:

- Use real Suq components and plausible, localized sample data.
- Display product previews straight-on, with usable controls and readable labels. Avoid decorative browser chrome, device tilt, fake navigation buttons, or static cards styled as interactive controls. Use typography, whitespace and subtle surface elevation rather than framing every section with borders.
- Pair the hero copy with an editable record-review surface. Beneath it, show one large chart with a row of selectable metrics and an adjacent stock-risk list. Metric tiles are controls: the selected tile has a distinct state, and changing it updates the chart, units, current observation, accessible value, and data table together.
- Highlight one interaction per mockup: upload review, live dashboard update, stock warning, or mobile quick entry.
- Keep sample merchant names fictional and clearly generic. Do not use real customer data.
- A mockup caption states the user benefit, not the component name: "Confirm what every column means before it affects your totals."
- Every screenshot has meaningful alt text; decorative device chrome is ignored by assistive technology.

3.8 Data-visualization language

Charts should look calm but never be vague.

- Ink is the primary series. Aqua, Lavender, Mint, and Amber are ordered supporting series.
 - Coral is reserved for risk or negative exceptions, not the fourth category in a palette.
 - Axes and grid lines use Mist/Slate at accessible contrast; labels remain readable at 200% zoom.
 - Tooltips show full date, localized number, unit/currency, comparison, and data freshness.
 - Legends are interactive only when keyboard and screen-reader equivalents exist.
 - Time-series charts never truncate the y-axis when the visual implication would be misleading.
 - Donuts aggregate small categories into "Other" and are not offered for high-cardinality dimensions.
 - Missing data uses gaps and an explicit "No data recorded" annotation, not zero.
 - Forecasts use a dashed line and shaded confidence band with a text legend.
 - Every chart offers a table render or accessible data summary.
-

4. Voice, message, and copy system

4.1 Voice

Suq speaks like a capable operator beside the merchant: concise, specific, calm under failure, and never condescending.

Situation	Voice	Example
Marketing	Clear and optimistic	"Your records already know what happened. Suq helps you see it."
Guidance	Direct and explanatory	"Choose the column that identifies an item. This unlocks item-level sales and stock views."
Success	Useful, not celebratory theater	"1,248 rows added. 36 duplicates skipped."
Warning	Consequence first	"This looks unlike your usual sales file. Review it before stock totals change."
Error	What happened + recovery	"We could not find a table in this image. Retake it in brighter light with the full page visible."
Empty state	Explain value + one action	"Retention needs a customer identifier. Assign one in Data review."
Upsell	Exact capability, no pressure	"View more than 90 days. Premium keeps your full history available."

4.2 Terminology

Prefer user language consistently:

- **Add data** as the broad action; use **Upload file**, **Paste table**, **Take a photo**, or **Enter manually** as methods.
- **Channel** is a saved, named stream with declared intent. Explain it on first use: "A channel remembers what this kind of data means."
- **Data review** in navigation and headings; "domain model" stays in technical documentation.
- **Field meaning** or **Used as** in forms; "semantic role" stays in help content.
- **Undo load** in the interface, with an explanation that all rows from that load and affected totals will be recalculated.
- **Dashboard** for a named canvas; **widget** for a movable question/answer frame.

4.3 Headline bank

Primary recommendation:

Know what’s selling. See what runs out next. See who comes back.

Alternatives for testing:

- **Your business is already speaking. See what the numbers say.**
- **From the records you keep to the answers you need.**
- **A clearer market day starts with the data you already have.**
- **Messy records. Clear next moves.**

Supporting lines:

- “No rigid template. Suq understands the structure, shows you its interpretation, and waits for your confirmation.”
- “Sales, stock, and returning customers—one daily workspace built around your business.”
- “Upload once or record the day as it happens. Your canvas updates as new data lands.”

4.4 CTA hierarchy

Intent	Primary label	Secondary label	Avoid
First visit during preview	Explore the demo	How it works	Start free or Log in leading to an unavailable action
First visit after authentication ships	Start free	Explore the demo	Get started, Learn more everywhere
Skeptical evaluator	Try sample data	See how review works	Upload your private data before trust is established
Returning visitor	Log in	Compare plans	Sign in / Log in mixed inconsistently
Empty dashboard	Add your first data	Try a sample	Configure dashboard first
Data ready	Review fields	View source	Continue without describing the next step
Premium boundary	Unlock full history	Compare plans	Upgrade now with artificial urgency

Any claim such as “no credit card required,” “setup in five minutes,” customer counts, accuracy percentages, or money saved requires verified evidence before publication.

5. Landing-page architecture

5.1 Page narrative

The landing page follows a simple persuasion sequence:

Recognition	"That is my problem."
↓	
Comprehension	"I understand what Suq does."
↓	
Trust	"It will not silently corrupt my numbers."
↓	
Relevance	"It answers the questions I ask every day."
↓	
Proof	"This works for businesses like mine."
↓	
Low-risk action	"I can try it safely."

The preview navigation contains **Product** · **How it works** · **Plans** · **FAQ**, language, and **Explore the demo**. Each section link opens the landing page, scrolls to its destination, and moves keyboard focus there. Focus must not draw a rectangle around the entire section: suppress the section outline and underline its heading when `:focus-visible` applies. Interactive controls retain their own focus indicators. Below 68rem the scrollable mobile menu retains demo-first focus and Escape restoration; links close the menu before focusing their destination. Production account links appear only after the account journey works; do not create placeholder navigation destinations.

5.2 Section blueprint

0. Announcement strip

The preview has no announcement strip. Source-format copy belongs in the hero and source section. Add an announcement only for a real, timely update; availability and privacy qualifications must remain visible at every viewport.

1. Hero: the daily promise

Eyebrow: "For the records you already keep."

Headline: "Know what's selling. See what runs out next. See who comes back." The last line describes observable retention, without promising that analytics alone causes repeat purchases.

Deck: "Preview a daily view of sales, stock, and returning customers from spreadsheets, POS exports, or a photo of your ledger."

Action during preview: lime **Explore the demo**, consistently used in the header, hero, briefing, and closing invitation. No public navigation promotes unavailable signup or login actions. Direct account-preview routes remain truthful. Once authentication and first use are verified on staging, the production CTA hierarchy applies.

Reassurance: “Fictional sample data · No account needed.” Place it once beside the hero CTA. Preserve contextual qualifications for estimates and unavailable analyses.

Composition: a flat two-column layout with top-aligned copy and compact briefing. Paper, Ink, Lime, Mint, and the serif emphasis retain the Suq identity. The briefing contains the merchant and date, “What needs my attention today?”, one answer sentence, three stat tiles, and one demo action. Revenue and the previous-day comparison lead; stock attention and returning customers follow. No chart, field-review controls, or second full-width dashboard extends the hero.

Evidence: sample revenue and customer totals come from the shared fictional fixture. The comparison names the previous day at the same time. Stock risk is explicitly an estimate at the sample sales pace. Display all amounts in the fixture's currency, formatted for the selected UI locale; changing language does not convert money.

Demo destination: the existing interactive dashboard retains metric selection, deterministic cumulative observations, keyboard-operable range control, chart table alternative, and stock details. “Review the sample records” opens a focus-managed disclosure below the dashboard. It contains the original Spanish CSV values, editable field role, confirmation, and reset. This local interaction never saves or uploads data. The landing page keeps one concise ambiguity example in the trust section; detailed interpretation controls are available through demo disclosures.

Interaction: a short briefing entrance is optional; reduced-motion users see the static final state. Keep keyboard focus visible, use shared dropdowns, and stay within the initial JavaScript budget.

Mobile acceptance: at 390×844 and default text size, show the header, eyebrow, headline of at most four lines, one-sentence deck, primary CTA, and a complete revenue tile with comparison in the first screen. The secondary CTA is not required. Stack naturally at narrower widths or expanded text; never clip content or shrink touch targets to satisfy a fold measurement. Validate English, Spanish, and French independently. Main sections remain flat against the page background.

2. Three daily merchant decisions

Immediately after the compact hero, show three concise rows with a merchant question, decision-oriented copy, and an inspectable example. Use flat section surfaces and fine rules; reserve contained backgrounds for evidence. Numbered benefits are removed because they are not a sequence.

One disclosure at the section heading identifies Mercado Norte, the sample date, and fictional data. Stock estimates and unavailable analyses retain their contextual qualifications. All explanatory copy and product labels render in English, Spanish, and French; original source records retain their values and currency.

- **What is selling?** Show the revenue increase in EUR cents, with a disclosure of current and previous-day product totals at the same 14:00 cutoff. Canvas Tote, Ground Coffee, and Other products sum to the same revenue as the hero and demo. The evidence identifies confirmed sales transactions and the period being compared.
- **What is about to run out?** Show Ground Coffee with 12 units left: a physical count of 50, plus 10 delivered, minus 48 sold. The six-units-per-day pace gives an illustrative two-day estimate, consistent with the demo risk list. Explain that a sales file alone cannot establish shelf stock.

- **Which customers come back?** Show 38 returning customers out of 241 distinct current identifiers; 203 are first seen in the available fictional history. A labelled checkbox removes identifier availability and replaces the count with an explained unavailable state, never zero. Evidence explains the match against earlier history without claiming a customer's lifetime relationship with the business.

3. Add → Confirm → See, including live entry

Replace the long landing-page workflow panels with three short numbered steps and a compact next-sale example. A source ribbon names familiar inputs; the detailed ten-format explorer remains reachable through a demo disclosure.

Narrative: “Bring a file. Or record the next sale.” Uploaded and entered data serve the same merchant decisions in the product design. The current interaction is explicitly local and does not claim a live API or offline queue.

Two-tap example: select one Ground Coffee sale, then confirm the displayed stock transition from 12 to 11. Selection alone does not change stock. Cancel returns to the initial state. After confirmation, Undo restores 12 and allows the example to be repeated. The next-sale example starts after the historical sample cutoff and changes only its own stock display, not the historical dashboard's revenue or customer totals.

Keyboard focus follows the current action through preview, confirmation, cancellation, and undo. A polite status announces the stock value. Values are derived from the explicit interaction state and shared fixture, so repeated confirmation cannot silently record extra sales. There is no network request or persistent record.

4. Trust: the answer comes with its evidence

Present one compact interpretation example after the business outcomes: “What does ‘Cod.’ mean?” This abbreviation occurs once in rendered landing copy, in the trust heading. Original sample values remain visible, but the detailed field controls, source table, confirmation, and reset belong in the demo. The trust copy explains why repeated codes still need the merchant's context and why absent cost means unavailable margin rather than zero.

The review link navigates to `/demo#demo-review`, opens the disclosure, moves focus to its summary, and scrolls to it. The source-explorer link does the equivalent for `/demo#demo-sources`. The full legacy step-by-step review remains available in a separate demo disclosure, preserving its field and evidence interactions without repeating them on the landing page.

Remaining blueprint: dashboard composition and expanded customer proof below remain future work. The compact comparison, planned plans, FAQ and working footer destinations are implemented as described below; delivery follows `docs/landing-page-revision-plan.md`.

8. Composable dashboard: “Your morning check is not your weekly review”

Body: “Start with a useful dashboard, then move, resize, rename, or render each question the way you think. Keep separate dashboards for different routines.”

Mockup sequence:

1. Default canvas after first upload.
2. Widget picker previewing the merchant's own data.
3. “Weekly review” dashboard with retention and customers.

4. Mobile reorder list.

Callout: “Changing a chart style does not recalculate the data.”

Premium boundary: one dashboard is free; multiple named dashboards are premium. Explain without interrupting the demonstration.

9. Global readiness

Headline: “Local conventions. One reliable model.”

Show the same compact metric in English, Spanish, and French with appropriate number, date, and currency conventions. Include timezone/day-boundary explanation.

Do not use flags. Use language names in their own language: English, Español, Français.

10. Proof

At pre-launch, use **product proof**, not fictional social proof:

- An interactive sample dataset.
- A supported-source matrix.
- A short explanation of tenant isolation and EU data residency.
- A measurable product standard: dashboard target under 300 ms p95, clearly labeled as a target until production evidence exists.
- A transparent “How interpretation works” page.

After beta, replace or supplement with approved customer evidence:

- One quantified case study tied to an auditable method.
- Short testimonials with name, role, business, locale, and consent.
- Customer logos only when contractual approval exists.

11. Comparison: keep your records

Show two short columns before the plans: working across separate records (compare exports, look up earlier entries, join sales and stock manually), and the planned Suq workflow (review field meanings, use a common daily view, retain evidence). This describes a concrete task rather than claiming all spreadsheets or competitors lack a capability. Keep the section flat and compact.

12. Planned plans

The preview displays two equal-weight, non-purchasable cards: **Free • planned** and **Premium • planned**. State prominently that accounts/subscriptions are unavailable and Premium pricing will be announced when finalized. No invented price, tax amount, discount, purchase control or trial claim.

- Free: one dashboard, 90-day visible history, five uploads per day up to 10 MB each, dashboard alerts, owner only, contextual sponsorship. Sync API and full exports are Premium capabilities.
- Premium: multiple named dashboards, history beyond 90 days subject to the stated retention rules, 50 uploads per day up to 50 MB each, dashboard/opt-in email/SMS alerts to a verified phone (up to ten SMS daily), owner plus up to four staff, Sync API, CSV/XLSX exports up to five jobs daily, and an ad-free workspace.

- A visible note states the six-week forecasting prerequisite and moving-average fallback, and labels priority support as planned rather than an active preview service.

Each card uses a heading and definition list. Stack at narrow widths; use two columns from 52rem. Keep the entire limits comparison visible rather than hiding limits in tooltips.

13. FAQ

Six native `details / summary` disclosures, initially closed, cover current availability; file sources and column names; uncertain fields, corrections and undo; missing stock/customer/cost evidence; history and downgrades; and current demo privacy. Multiple answers may be open. Preserve keyboard toggling, visible focus, enlarged text and all three locales.

Distinguish planned product behavior from the working fictional demo in each relevant answer. State the retention distinctions from SDLC §2.2 and the data model: Free raw records beyond 90 days are pruned nightly; Premium-era records hidden on downgrade are retained 13 months; original uploads expire after 30 days on Free or 180 days on Premium. Do not promise perpetual retention.

The privacy answer describes only the inspected preview: no business-file input, browser-persisted language, temporary in-tab journey events with no analytics collector, and ordinary page requests to the host. Production privacy terms and a public support channel are not yet published here. This is an explanation of the preview, not a legal policy or a verified production-security claim.

14. Final CTA and footer

Headline: “Your next clear decision is already in your records.”

Preview action: Explore the demo. Restore **Start free** with **Explore the demo** as secondary only after the production account journey is verified.

The current footer links only to the working demo, Plans and FAQ, alongside the brand and language information. Approved public support and privacy/terms destinations remain a publishing dependency; do not invent an email, legal policy, company identity or empty link. Future production footer groups may include Company, Legal, status and advertiser access after those destinations are verified.

5.3 Landing-page wireframe

This is the broader launch blueprint, including future sections. The current preview order is hero → three merchant decisions → short workflow and next-sale example → trust → workflow comparison and planned plans → FAQ → closing action.

Announcement: built for the records you already keep

Suq Product How it works Use cases Pricing Resources EN Log in [CTA]

COMMERCE CLARITY FROM YOUR DATA Interactive CSV field review
Know what's selling. See what runs out next.
See who comes back.
[Start free] [Explore the demo]

What needs my attention today? FICTIONAL SAMPLE DATA
Answer → [Stock risks] [Evidence] [Review Cod.]

Select metric → inspect time/chart/table · select stock → risk detail

CSV · Excel · Paste · JSON · POS · Marketplace · Image · PDF · Entry · API

DARK PROBLEM CHAPTER: illustrative merchant questions

Add → Confirm → See: one large stage; static workflow on mobile

WHAT IS SELLING?	product mockup
product mockup	WHAT WILL RUN OUT?
WHICH CUSTOMERS RETURN?	product mockup

BLACK TRUST PANEL: Nothing silently guessed

Channels + live entry Composable dashboard

Global readiness · Proof · Comparison · Pricing · FAQ
Inspectable outcome grid · Dark sample-demo invitation · Footer

6. Landing-page product mockups

The page should not rely on one repeated screenshot. Build a small mockup set from production components so changes stay synchronized with the product.

6.1 Hero briefing and demo dashboard

The landing hero uses the compact question, answer, and three-stat composition in §5.2. Revenue and its dated comparison form the first product cue on mobile. The full chart and review controls are reached through the demo.

The demo retains selectable revenue, transactions, units, and customer totals, deterministic chart series, keyboard-operated time inspection, a table alternative, and stock-risk detail. Its review disclosure contains the original sample rows, field-role selection, confirmation, invalidation on edit, and reset. All data remains fictional and local. Preview interactions never imitate a saved backend action.

6.2 Interpretation-review mockup

Show five columns with different states:

Source header	Detected type	Used as	Confidence	UI treatment
Fecha	Date, day first	Transaction time	High	Mint confirmation
Imp.	Decimal, EUR	Line amount	High	Evidence: quantity × price
Cod.	Identifier	Item identity	Needs confirmation	Amber review
Cliente	Text	Customer identity	Medium	Plain-language evidence
Notas	Text	Not used in analysis	High	“Preserved for filtering”

The selected row opens an evidence drawer: sample values, competing meanings, detected locale, effect on supported widgets, and an editable preview. For images, show the recognized cell beside its cropped source region.

6.3 Mobile quick-entry mockup

Show channel “Daily sales,” item autocomplete, quantity, amount, time, and a large **Save & add another** button. After save, the form retains stable context and clears changing fields. Offline state is explicit: “Saved on this device · will sync when connected.”

6.4 Trust and security mockup

Use a simple architecture illustration rather than a shield collage:

```
Your workspace → authenticated request → tenant scope → PostgreSQL RLS
raw file retained by policy      derived dashboard reads from rollups
```

Explain outcomes: workspace isolation, encrypted transport/storage configuration, hashed merchant-customer identifiers, EU data residency, audit history, and recoverable model changes. Final public wording requires security and legal review.

7. Marketing and growth initiatives

7.1 Acquisition themes

Theme A — The messy-data advantage

Content promise: “You should not have to rebuild your export before you can understand it.”

Initiatives:

- **Spreadsheet rescue kit:** localized guides for separators, date ambiguity, title rows, formulas, and duplicate exports.
- **Can Suq read this?** interactive sample gallery with deliberately messy, synthetic inputs and visible interpretation.
- **Data Clinic:** periodic live session where the team demonstrates safe interpretation on consented or synthetic examples.
- Search content around “analyze POS export,” “inventory from Excel,” “sales dashboard from CSV,” and localized equivalents.

Theme B — The three-question operating rhythm

Build campaigns around one daily routine:

- Monday stock check.
- Daily sales pulse.
- Weekly returning-customer review.

Each campaign has a dedicated page, demo dashboard template, short video, and downloadable checklist. The product should deep-link new users into the matching starter template after first data confirmation.

Theme C — Trust before automation

Publish clear explainers about confidence, field interpretation, deduplication, data provenance, load reversal, and why the system asks questions. This differentiates Suq from opaque “upload anything” claims.

7.2 Product-led acquisition

- **Instant sample workspace:** no private data required; visitors can explore a preloaded merchant and switch locale.
- **Shareable read-only insight image:** future initiative, only after privacy review and explicit user action. Default to no customer identifiers.
- **Starter templates by business type:** retail, food shop, marketplace seller, wholesaler. Templates choose widgets and suggested channel fields; they never impose a data schema.

- **Upload compatibility report:** after a safe dry run, show recognized fields, possible capabilities, and unresolved questions before account creation only if privacy/legal design permits temporary processing.

7.3 Activation and lifecycle

Moment	Message	Product destination	Success event
Email verified	"Let's turn one record into one answer."	Guided source choice	Source submitted
Upload stalled	Specific recovery based on stage	Existing upload job	Review resumed
Model ready	"We found 8 field meanings; 2 need you."	Data review	Model confirmed
First load complete	Lead with one insight, then counts	Starting dashboard	Insight viewed
Day 2 no return	"Your dashboard is ready when today's data is."	Add data	Second load
Repeated shape	Offer to save as a channel	Channel creation	Channel saved
Stock capability available	Explain what an observation channel unlocks	Channel setup	First stock count
Premium boundary	Name the exact blocked capability	Contextual comparison	Checkout started

Notification frequency and consent must be explicit. Operational verification messages are not marketing permission.

7.4 Conversion experiments

Run one variable per experiment and segment results by locale and acquisition source.

Hypothesis	Variant A	Variant B	Primary metric	Guardrail
Concrete outcomes outperform abstract clarity.	Three-question hero	"Messy records, clear decisions" hero	Qualified signup	Bounce and comprehension survey
A demo reduces data-trust anxiety.	Start free only	Start free + sample demo	First source submitted	Signup rate
Review proof improves activation.	Dashboard hero visual	Input → review → dashboard visual	Model-confirm rate	Hero load time
Contextual pricing converts better.	Pricing in nav	Pricing plus capability links	Checkout start	Support questions/refunds
Business templates reduce blank-canvas anxiety.	Generic starter	Business-type starter	First insight viewed	Template replacement rate

Do not optimize clicks at the expense of successful confirmed loads. The activation north star is a merchant reaching a correct first insight.

7.5 Funnel and content metrics


```
Landing view
→ meaningful demo interaction
→ signup started
→ email verified
→ source submitted
→ review completed
→ first successful load
→ first insight viewed
→ second data arrival
→ channel saved
→ retained weekly use / premium activation
```

Track abandonment and errors at every transition, segmented by source type, locale, device, and acquisition channel. Never send raw filenames, column names, values, customer identifiers, or dashboard contents to marketing analytics.

8. Authenticated product information architecture

8.1 Desktop navigation

The left rail is stable and task-oriented:



```
SUQ INSIGHTS

[Workspace switcher]
[Search / command menu]

TODAY
  Dashboard
  Enter data
  Alerts

DATA
  Channels
  Uploads
  Datasets
  Records
  Entities

MANAGE
  Reports
  Integrations      Premium when gated
  Settings

Help & support
User / plan
```

“Inventory” and “Customers” are not required as permanent top-level destinations at launch because their primary experience is widget-based. If dedicated analytical pages are later implemented, they may appear under an **Analyze** group after user research proves a need. The navigation should not imply unavailable screens just because the inspiration dashboard has them.

Desktop rail width: 264–280 px. At 1,024–1,279 px, collapse to a 76 px icon rail with labels available on focus/hover and an explicit expand control. Persist the preference per user.

8.2 Mobile navigation

Use a five-destination bottom bar:

- Dashboard
- Enter
- **Add** (prominent center action opening the source sheet)
- Alerts
- More

“More” opens Channels, Uploads, Datasets, Records, Entities, Reports, Integrations, Settings, support, workspace, plan, and account. Active state uses icon, label, and shape—not color alone. The bar respects safe-area insets and does not cover table actions or toasts.

8.3 Global command menu

Desktop shortcut `/` focuses search when not typing; `Ctrl/Cmd+K` opens a command menu. It searches navigation, dashboard names, widgets, channels, uploads, entities, and help actions within the user’s role and entitlements. Results are grouped and keyboard navigable. Recent results remain on device; server logs do not capture raw query terms when they could contain merchant data.

8.4 URL model

Every restorable view has a URL:

- `/app/dashboards/:dashboard_id`
- `/app/entry?channel=:channel_id&mode=quick`
- `/app/channels/:channel_id`
- `/app/uploads/:upload_id`
- `/app/datasets/:dataset_id/review`
- `/app/records?dataset=:id&sort=-occurred_at`
- `/app/alerts?status=active&severity=critical`

Filters, sort, selected tab, and stable date ranges live in the query string when sharing or reload should preserve them. Never place cursor tokens, sensitive source values, or temporary object URLs in a shareable link.

9. Dashboard concept

9.1 Dashboard job

The dashboard is a daily decision canvas, not a report index. In under ten seconds, it should answer:

1. Is the data current and trustworthy?
2. What changed?
3. What needs action?
4. Where can I inspect the evidence?

9.2 Desktop frame

Brand	Workspace / Dashboard			Help	User
Workspace ▾					
Search	Morning check ▾	7 days ▾	Compare ▾	Updated 2m ago	
	[Add widget] [Arrange] [...]			● Live	
Dashboard					
Enter data					
Alerts 3	What changed and why? narrative insight	Revenue +18%	Units +7%		
Channels					
Uploads					
Datasets	How is money coming in over time? line / bar / table			Attention 3 alerts sponsored*	
Records					
Entities					
Reports					
Integrations	What sells most? ranked bars	What should I buy today? stock/reorder table			
Settings					
Help	Data current through 14:32 · 4 sources · View freshness				

* Free tier only; clearly labeled Sponsored / Patrocinado / Sponsorisé.

9.3 Header anatomy

Global top bar: breadcrumb/workspace context, help, notifications, language, account. Height 64 px.

Canvas header: dashboard selector and rename, date range, comparison, freshness, live status. A second row holds Add widget, Arrange, Reset to template, and overflow actions. On small screens this becomes a sticky title row plus a filter sheet.

Date behavior:

- Presets: Today, Yesterday, Last 7 days, Last 30 days, This month, Last month, Custom.
- Dates use the merchant timezone; the selected timezone is visible in the custom picker.

- Comparison options: previous period, previous year when history permits, or off.
- Entitled history is enforced by the server; the free-tier boundary is shown at the unavailable calendar edge with an exact explanation.
- A change applies to widgets that inherit the dashboard range. Widgets with a custom range show a small “Custom” badge.

9.4 Starting canvas

After the first successful load, create a useful dashboard from supported capabilities:

1. `insight-summary` spanning 6–8 columns.
2. `headline-stat` tiles for available measures.
3. `revenue-over-time` or the best supported velocity question.
4. `alerts-panel` when alerts exist; otherwise `data-freshness`.
5. `top-items` when item identity exists.
6. `stock-status-table` only when stock can be derived honestly.
7. `repeat-vs-new` only when customer identity exists.
8. `sponsored` exactly once for the free tier, contextually placed.

Unavailable capabilities are explained in a compact recommendation region below the canvas, not represented by misleading zero widgets. Example: “Add a customer identifier to unlock returning-customer views.”

9.5 Widget anatomy

Every widget frame contains:

1. Drag handle visible in Arrange mode and keyboard-movable equivalent.
2. User-overridable title.
3. Short question or context label when the title is custom.
4. Freshness/partial-data indicator when different from the canvas.
5. Primary visualization or answer.
6. Comparison and unit context.
7. Optional insight or next action.
8. Header menu: change view, configure, duplicate, inspect data, rename, remove.
9. Resize handle in Arrange mode, plus a dialog with width/height choices for keyboard users.

Hover-only controls become persistently visible on touch. Widget menus use buttons with accessible names. Removing a widget offers a brief undo toast; it does not require a confirmation modal because the arrangement is recoverable.

9.6 Arrange mode

- Enter through a labeled **Arrange** button; the canvas background changes subtly and a persistent mode bar appears.
- Widgets display drag handles, size labels, and grid outlines.
- Dragging snaps to the twelve-column grid and reserves the proposed position.
- Collision moves affected widgets predictably down, never off-screen.

- Keyboard movement: focus handle, press Space to pick up, arrow keys to move, Space to drop, Escape to cancel. Screen-reader announcements state position and collisions.
- Autosave status cycles through “Unsaved changes,” “Saving...,” and “Saved.” A failed save stays visible with Retry and retains the local layout.
- **Reset to template** previews the changed arrangement and asks for confirmation; this is not undoable after the recovery window.
- Mobile uses a reorder list with Move up/down and size choices; no touch drag is required.

9.7 Widget picker

Open as a wide drawer on desktop and a full-screen route on mobile.

Structure:

- Search by question or concept.
- Groups: Sales, Items, Inventory, Customers, Cross-cutting.
- Filters: Supported now, All, Free/Premium, data required.
- Each card shows the question, recommended render, required concepts, live preview from merchant data, and whether it is already placed.
- Unsupported cards remain discoverable but explain exactly what data concept is missing. They do not show sample values that could be mistaken for the merchant’s data.
- Selecting a supported card previews available renders and configuration before placement.
- Placement chooses the first suitable open position while keeping the new widget in view and moving focus to it.

9.8 Dashboard selector and templates

- Selector lists personal dashboards, workspace template, locked premium dashboards after downgrade, and Create dashboard.
- Dashboard names are 1–80 characters, unique per user after normalization, and validated inline.
- Free users see one active dashboard. Extra dashboards retained after downgrade are visible but read-only with an explanatory lock state.
- Creating from a template previews included questions and data requirements.
- Publishing a workspace template is owner-only and warns that existing personal dashboards will not be overwritten.

9.9 Live updates

The canvas status communicates connection without distraction:

- **Live:** small static green dot and “Live.” No constant pulsing.
- **Updating:** affected widget shows a subtle progress line; existing values remain visible.
- **Updated:** changed values briefly highlight for at most 1.2 seconds unless reduced motion is active.
- **Offline:** persistent amber banner: “You’re offline. Dashboard values are from 14:32.”
- **Reconnecting:** retain content, retry with backoff, and offer manual Retry after a reasonable delay.

- Events are coalesced; the interface never flashes once per entered row.

9.10 Widget states

State	Visual	Copy/action
Loading, first view	Skeleton matching final geometry	<code>aria-busy=true</code> ; no indefinite spinner
Refreshing	Existing data + top progress line	“Updating” in accessible status region
Ready	Answer + context + freshness	Optional Inspect data
Empty, no events in range	Empty chart frame with zero-state annotation	“No sales recorded in this period. Try a wider range.”
Unsupported capability	Neutral explanatory card	“This view needs an item identifier. Review fields.”
Partial data	Amber inline notice	“2 of 4 sources include quantity; unit totals are partial.”
Stale	Amber freshness badge	“Last updated yesterday · Add data”
Widget failed	Error contained in frame	“This answer could not load. Retry.” + request ID in details
Permission denied	Locked frame, no leaked data	“You do not have access to this dashboard.”
Premium locked	Readable explanation, no blurred fake data	Exact benefit + Compare plans
Deleted source/ reversed load	Recomputed answer and audit note	“Changed after load ‘Monday count’ was undone.”

9.11 Dashboard personalization boundaries

Users can move, resize, rename, configure, switch render, duplicate, and remove widgets. They cannot redefine metric formulas inside the dashboard. A render choice changes only presentation and never triggers a new backend calculation when the existing payload supports it. Configuration that changes the question—period, measure, items, segments—requests a new payload and updates the cache key.

10. Launch widget presentation

The SDLC's widget catalog is authoritative. The interface presents each widget as a question and offers only sensible renders for its data shape.

10.1 Sales velocity

Widget	Default presentation	Key UX details
Revenue over time	Line with comparison	Localized money; visible currency; range/granularity; data gaps; Inspect records.
Transactions over time	Bars	Whole counts; interval tooltip; comparison as outline/secondary series.
Units over time	Line	Unit label and partial-data warning when not all sources resolve quantity.
Headline stat	Large value + delta	Period label is always visible; delta states its comparison basis.
Insight summary	2-4 sentence narrative	Every claim links to the supporting widget/filter; no invented causal language.
Sales by period pattern	Heatmap	Accessible table toggle; timezone shown; intensity legend includes values.

10.2 Item performance

Widget	Default presentation	Key UX details
Top items	Ranked horizontal bars	Top N; "Other" where relevant; revenue/units/transactions toggle; full names on focus.
Item mix	Stacked bars	Avoid donut when categories exceed the readable threshold.
Item detail	Data table + sparkline	Column controls, cursor pagination, sticky item identity.
Item trend comparison	Multi-line	Limit selected items; direct labels when space permits.
Slow movers	Table	Define "slow" visibly and allow stock-on-hand filter.

10.3 Inventory

Widget	Default presentation	Key UX details
Stock status	Table with severity bands	Status label + icon + color; expandable provenance; last observation date.
Days of stock	Gauge/bullet	Exact day estimate beside visual; “Insufficient history” is not zero.
Depletion forecast	Timeline	Forecast method and horizon in details; confidence band; stock-out marker.
Reorder list	Checklist table	User check state is local workflow state, not proof an order was placed.
Stock value	Stat/category bars	Only available when the required valuation basis is confirmed.

10.4 Customers

Widget	Default presentation	Key UX details
Retention cohort	Heatmap	Cohort definition and horizon; accessible table; no raw customer identities.
Repeat vs new	Stacked area	Explain classification; count/revenue toggle.
Top customers	Ranked bar/table	Use workspace-safe display identifiers; respect privacy model.
Purchase frequency	Histogram	Bucket definition and selected period visible.

10.5 Cross-cutting

Widget	Default presentation	Key UX details
Alerts	Status list	Severity, plain-language reason, time, acknowledge; rules link.
Data freshness	Stat/timeline	Latest source, coverage, stale threshold, Add data action.
Record table	Table	Any retained attribute filter, cursor pagination, export entitlement.
Segment comparison	Grouped bar	Segment definition always displayed; accessible table.
Sponsored	Clearly labeled card	At most one per page view; contextual, localized label; collapses cleanly when absent.

10.6 Future-only analytics

The reference dashboard and common ecommerce products often show profit, margin, returns, fulfillment, ad spend, ROAS, CAC, cash flow, and geography. These are visually tempting but are not launch metrics merely because a card can be drawn. Add them only after the SDLC defines their source concepts, formulas, correction behavior, entitlement, privacy rules, and test fixtures. Margin analysis is a likely later widget once cost data is commonly present.

11. Critical supporting screens

11.1 Guided empty dashboard

The empty canvas is an onboarding screen, not a blank grid.

Headline: “Let’s turn one record into one useful answer.”

Body: “Add a file, paste a table, take a photo, or try a sample. Suq will show what it understands before anything affects your dashboard.”

Primary: Add data. **Secondary:** Try a sample.

Below, show the three future questions with muted illustration and requirements. A four-step progress rail—Account, Profile, Add data, First insight—makes the journey finite. Do not show the widget picker until at least one supported capability exists.

11.2 Add-data sheet

Accessible from the global Add action. Choices are large cards:

- Upload a file.
- Paste a table.
- Use a photo or PDF.
- Enter data.
- Send to a channel.
- Connect with the Sync API (premium).

Each choice states supported types, size limit from active entitlement, privacy note, and expected next step. Drag-and-drop is an enhancement; a standard file button remains available. Upload progress survives navigation and announces milestones without reading every percentage.

11.3 Upload progress

Use stage language: Uploading → Checking safety → Reading structure → Understanding fields → Waiting for review → Processing → Complete. Show determinate progress only when real; otherwise show the current stage and elapsed time. Closing the panel does not cancel the job. Cancellation, when safe, is explicit and scoped.

11.4 Data review

Desktop structure:

Back to upload	Review "sales-september.csv"	Saved draft
8 fields recognized · 2 need review · Supports: revenue, units, items Missing: customer identity → retention unavailable		
Field list/table source · type · used as confidence · status	Evidence and live preview sample values · competing meanings parsed table / source crop	
[Save draft]	[Confirm and process]	

Details:

- The first unresolved field receives focus only after the summary is announced.
- Confidence uses High / Medium / Needs review plus evidence, not a mysterious percentage alone.
- Editing type, role, unit, currency, date order, constant, split/combine, exclusion, identifier, or cell re-renders a real preview.
- Conflicting roles are prevented or explained before confirmation.
- Sticky footer summarizes consequences: supported analyses, unresolved warnings, excluded fields, and the primary action.
- On mobile, fields become a step list; evidence opens as a full-screen detail. The user can move Next unresolved / Previous without returning to the list.

11.5 Result summary

Lead with what happened:

"1,248 rows added. 36 duplicates skipped. 4 rows need correction."

Then show one concrete insight, **View dashboard**, **Download error report** when needed, **Undo this load**, and an offer to save a recurring shape as a channel at the correct moment. If more than half of rows fail, do not present a partial success; return to review with specific guidance.

11.6 Channel detail

Tabs: Overview, Add data, Field setup, Load history, Entry form, Guard decisions.

Header shows channel name, intent label, fill policy, last arrival, expected cadence, and status. Changing intent is high consequence: preview the derived-state impact and require explicit confirmation. Load history uses cursor pagination and exposes counts, source, author, status, model version, errors, and Undo when allowed.

11.7 Entry space

Modes: Quick, Batch, Corrections.

- Quick prioritizes recent items, barcode/identifier focus when supported, Save & add another, and visible offline queue.
- Batch resembles a spreadsheet but preserves native form semantics, row errors, keyboard movement, paste, and undo.
- Corrections show original value, revised value, author/time, reason, and downstream recalculation state.
- Concurrent updates arrive unobtrusively; editing collisions are explained before overwriting.

11.8 Alerts

Default list groups Active, Acknowledged, and Resolved. Each item includes severity, what happened, affected entity, time, recommended inspection, delivery channels, and acknowledgement. Filters persist in URL. Free users can use dashboard alerts; premium channel toggles explain email/SMS prerequisites and exact unlock.

11.9 Records and entities

Records are a dense, inspectable evidence surface. Fields can include retained unmapped attributes. Entities support duplicate review and merge previews. Cross-links preserve the originating dashboard range/filter so the merchant can move from answer to evidence and back without losing context.

11.10 Settings

Groups: Profile and locale, Workspace, Team, Notifications, Billing and plan, API keys, Security, Data and privacy. Owner-only items are absent or clearly read-only for staff; never show a control that fails only after submission. Destructive actions live in a separated danger region with consequences and recovery limits.

12. Component behavior in detail

12.1 Buttons

- One primary button per panel or sticky action region.
- Primary: lime fill, Ink text. Hover darkens border; active compresses at most 1 px; focus uses a 3 px accessible outline.
- Secondary: white or transparent, Ink border/text.
- Tertiary: text/icon, reserved for low-emphasis actions.
- Destructive: Coral only in confirmation context; neutral trigger before confirmation where possible.
- Loading button keeps its width, shows progress, and retains a verb such as “Processing...”; disabled state is not used as the only explanation.

12.2 Forms

- Labels sit above fields and remain visible after entry; placeholder text is an example, never the label.
- Required/optional is textual. Error copy sits below the field and is summarized at the top after submit.
- Validate on blur for local format errors and on submit for cross-field rules; avoid scolding on the first keystroke.
- Currency fields display currency separately and parse locale conventions safely.
- Date inputs support keyboard entry and a calendar; day/month ambiguity includes an example.
- Autosaved drafts show timestamp and recovery. Sensitive tokens are never restored into visible fields.

12.3 Tables

Anatomy:

- Search/filter region above, active-filter chips, result count, column control, density, export where entitled.
- Sticky header; first identity column may pin on wide screens.
- Sort button includes direction and priority; default sort is visible.
- Row selection persists only within the explicit action scope and announces the count.
- Row actions use a visible overflow button and remain keyboard accessible.
- Long values truncate visually but expose full text on focus and through an accessible detail—not title attribute alone.
- Empty result after filtering offers **Clear filters**; true empty state offers the relevant creation action.

- Virtualization is allowed for large loaded windows only when screen-reader and focus behavior are proven.

12.4 Cursor pagination

The API is cursor-based and caps page size at 100. The interface must not pretend stable numbered pages exist.

Default table pattern: 50 rows, **Previous** and **Next** buttons, “Showing 51–100” when a reliable running count is known, and optional page-size choices 25 / 50 / 100. The opaque cursor remains internal.

Feed/timeline pattern: **Load more** appends the next cursor window and preserves scroll position. Infinite loading may supplement but never replace the explicit button.

Rules:

- Filter, sort, dataset, and date changes reset to the first cursor and update the URL.
- Back navigation restores loaded windows and scroll position from session state where practical.
- Previous uses the server-provided previous cursor; clients do not construct cursors or infer offsets.
- Disable Next only when the response proves there is no next cursor.
- On error, retain existing rows and offer Retry at the pagination control.
- Selection across windows must either be explicitly supported server-side or described as “selected on this page.”
- Screen readers hear newly appended row counts through a polite live region.
- Exports are asynchronous and are not implemented by looping through visible pages in the browser.

12.5 Filters

- Applied filters are visible as removable chips and represented in the URL.
- Desktop uses an inline primary row plus a filter drawer for advanced criteria; mobile uses a full-screen sheet.
- The Apply button states the result count when cheaply available; Clear all requires no confirmation.
- Numeric/date filters show units/timezone. Attribute filters name the dataset/source context.
- Saved views are future scope unless explicitly scheduled; dashboard widget configuration is not a substitute.

12.6 Search and autocomplete

- Debounce remote search around 250–350 ms and cancel superseded requests.
- A minimum query length is communicated when required.
- Matching text is highlighted without changing the accessible name.
- Entity autocomplete distinguishes exact identifier matches, normalized-name matches, and “Create new.”
- No results explains the query scope and offers a relevant next action.

12.7 Drawers, dialogs, and sheets

- Use a dialog for a decision that blocks background interaction; use a drawer/sheet for inspection or configuration that benefits from context.
- Focus moves to the heading or first meaningful control, stays trapped for modals, and returns to the trigger.
- Escape closes non-destructive overlays. Unsaved destructive edits ask before closing.
- Mobile drawers become full-screen sheets with a visible Back/Close action.
- Deep, multi-step tasks such as data review use routes, not nested modals.

12.8 Toasts and banners

- Toasts confirm lightweight, recoverable actions and remain long enough to read. Important failures also remain near the failed object.
- Undo toasts last 8–10 seconds and pause on hover/focus.
- Banners communicate persistent system conditions: offline, verification required, payment grace, upload incident.
- Never stack more than three toasts; combine repetitive live events.

12.9 Status and progress

Statuses use icon + text + color: Draft, Waiting for review, Processing, Complete, Complete with errors, Paused, Failed, Reversed. Progress labels describe stages. A percentage appears only when backed by measurable work. Time estimates are ranges and disappear when confidence is poor.

12.10 Empty, loading, and error states

Every screen defines four distinct states before implementation:

1. **First use:** explain value and offer creation/sample action.
2. **No results:** preserve query context and offer Clear filters.
3. **Unavailable capability:** name the missing data concept and link to review.
4. **Failure:** preserve safe content, state what failed, offer retry/recovery, include request ID in expandable details.

Skeletons must approximate final layout to prevent shifts. After 10 seconds, replace silent skeletons with stage or recovery copy. A global error page is reserved for shell failure; widget and panel failures stay local.

12.11 Permission and entitlement states

Authorization is server-enforced. The UI improves comprehension but is never the security boundary.

- Hidden: actions irrelevant to the role, such as billing for staff.
- Disabled with reason: a temporarily unavailable action the user can resolve, such as SMS before phone verification.
- Locked with comparison: premium capability at the point of intent.

- Not found: cross-tenant identifiers or resources the user must not know exist.

12.12 Confirmation patterns

Action	Confirmation	Recovery
Remove widget	No modal	Undo toast
Delete dashboard	Named confirmation	Soft-delete recovery window if supported
Undo load	Impact preview + explicit confirm	Audit trail; re-add source if needed
Change field meaning after commit	Re-derivation preview + confirm	Versioned model rollback
Change channel intent	Derived-state impact preview + confirm	Version/audit-based recovery
Revoke API key	Confirm key name	Irreversible; create replacement
Leave unsaved review	Confirm only if draft cannot safely persist	Saved draft preferred

12.13 Dropdowns and selection surfaces

One visual family, appropriate semantics. All web dropdowns inherit this contract, including language, field meaning, dashboard, workspace, filters, profile, and overflow controls as those features ship. Current coverage includes the shared public-header language picker (landing, demo, signup, login and mobile navigation), the demo field-role picker, and the interpretation-review field-role pickers. Future authenticated menus remain planned, not simulated.

Surface and rows: White floating panel, 16 px card radius, the shared overlay shadow, 8 px internal padding, and 8 px rounded rows. Avoid heavy panel outlines and repeated separators; use spacing and optional contextual headings to group content. Use Ink text and Slate supporting text. Selection combines a pale Mint surface with a Forest checkmark, never color alone. Keyboard-active rows have a visible Forest outline distinct from the saved selection. Options are at least 44 px high, wrap translated labels, and may carry a meaningful monochrome mark. Language options show names in their native language, not flags.

Shared implementation: `apps/web/src/components/dropdown-select.tsx` and its co-located vanilla CSS own finite, single-value selection. Callers supply localized labels, options, optional marks/hints, disabled state, value and change handler. Do not fork copies for landing or dashboard pages. Empty option sets disable the trigger; data-loading, error and retry messages belong to the owning form and must be visible before a remote picker is enabled. Searchable or multi-select controls require their own accessible interaction contract rather than adding untested behavior to this primitive.

Selection behavior: Use a named select-only combobox controlling a listbox with explicit selected and disabled option states. DOM focus stays on the trigger while `aria-activedescendant` identifies the navigated option. Enter/Space opens or commits; Arrow keys browse enabled options; Home/End jump to the first/last enabled option; printable characters support prefix search and repeated-character cycling. Tab commits the active option and moves onward. Escape closes without changing the value and does not close the parent mobile navigation. Clicking an enabled option commits it; outside interaction dismisses without committing. A reopened list starts at the saved selection. Browsing must not invalidate a review; an actual change still invalidates any prior local confirmation.

Position and motion: Render popups outside clipping containers, align with the trigger, flip above when necessary, constrain them to the viewport, and scroll long lists internally. Recalculate geometry on scrolling, resizing, and visual viewport changes. Use 120 ms opacity/4 px motion with no bounce; reduced motion removes animation. Forced-colors mode adds a visible panel/control outline and retains non-color selection checks. At narrow or zoomed widths, every option remains reachable without horizontal page scrolling.

Menus are not selects: Future profile/action menus may reuse the surface, contextual identity header, row spacing and icons, but use menu-button/menuitem semantics for commands or ordinary links for navigation. Do not implement logout, deletion or route links as listbox options. Group destructive actions separately with a text label and the relevant confirmation rule in §12.12. Long filters and complex date selection use the documented sheet/dialog patterns. React Native uses platform-appropriate accessible pickers or sheets and shared visual tokens, not the web popup or CSS.

Validation: Cover click/touch, typeahead, disabled options, outside dismissal, Tab/Shift+Tab, Enter/Space, Escape within mobile navigation, focus retention and selected-state announcements. Audit open and closed states in all three locales, 30–40% expansion, 320–1440 px layouts, 200%/400% reflow, reduced motion, forced colors, viewport edges and long-list scrolling. Browser automation supplements but does not replace NVDA/VoiceOver and real mobile screen-reader checks before release. The keyboard contract is informed by the [WAI-ARIA select-only combobox guidance](#); the reference example is not copied as a production component.

13. Responsive behavior

13.1 Breakpoints

Range	Grid	Navigation	Canvas behavior
0–479 px	4 columns, 16 px gutter	Bottom bar	Single-column widgets; compact controls; full-screen sheets
480–767 px	4 columns, 20 px gutter	Bottom bar	Single-column widgets; wider charts; reorder list
768–1023 px	8 columns, 20 px gutter	Collapsible drawer/rail	Widgets may span 4 or 8; touch-friendly arrangement
1024–1279 px	12 columns, 20 px gutter	76 px compact rail	Dense canvas; secondary actions in overflow
1280 px+	12 columns, 24 px gutter	264–280 px rail	Full canvas controls and previews

Breakpoints respond to available space, not device labels. Test at zoomed widths and with the French locale.

13.2 Landing-page adaptation

- The preview hero uses a responsive 27–45 px headline on compact widths, with a four-line maximum target at 390×844 in all three locales at default text size. Larger text must reflow naturally rather than being clipped.
- The preview hero has one primary demo CTA; a secondary action is not required in the first screen.
- Product visuals crop to the decision being explained rather than shrinking an entire desktop dashboard into illegibility.
- Horizontal card rows use snap scrolling only when all cards remain reachable by keyboard and a non-gesture control exists.
- Decorative haze and marks disappear before content or contrast is compromised.

13.3 Dashboard adaptation

- Widgets follow their saved reading order in one column on phones.
- Desktop x/y position does not determine an inaccessible mobile order; the stored order is explicit.
- Tables first reduce optional columns, then switch to a row-detail pattern. Essential identity, value, status, and action remain visible.
- Chart tooltips support tap and keyboard; a table toggle is adjacent.

- Date range and dashboard actions move into sheets without losing current values.
- Mobile arrangement uses a reorder list and size presets; freeform drag is not required.

13.4 Low bandwidth and older devices

- Marketing initial JavaScript remains under the SDLC budget; the hero is meaningful before hydration.
 - Dashboard shell and last successful values may render from safe client cache while freshness is verified.
 - Charts load per visible widget and avoid rendering off-screen canvases unnecessarily.
 - Images use responsive formats and dimensions; mockups do not load 4K assets on mobile.
 - Offline entry is visibly queued. Dashboard offline mode never implies current data.
-

14. Accessibility specification

Target WCAG 2.1 AA across merchant-facing screens.

14.1 Foundations

- Semantic landmarks: header, nav, main, complementary only when truly secondary, footer.
- One descriptive H1 per route; widget titles follow a coherent heading level.
- Skip link to main content and, on dashboards, optional skip to canvas controls.
- Visible focus at 3:1 contrast, never removed.
- Text and controls meet contrast requirements; chart distinctions do not rely on color.
- 200% text zoom and 400% browser zoom retain functionality without two-dimensional scrolling except genuine data tables.
- Touch targets are at least 44 × 44 px.

14.2 Charts

- Each chart has a concise accessible summary: metric, period, direction, extrema, and missing-data note.
- A table render is available from the widget header.
- Canvas/SVG marks are not the only source of information.
- Tooltip content is reachable by keyboard and dismissible.
- Patterns, direct labels, or line styles distinguish series where necessary.

14.3 Drag and drop

- Every drag action has keyboard and button alternatives.
- Pick-up, new position, collision, saved state, and cancellation are announced.
- Motion is reduced or removed under `prefers-reduced-motion`.
- Focus order follows reading order, not visual CSS placement alone.

14.4 Live regions

- Use polite announcements for save status, appended pagination rows, upload stages, and coalesced dashboard refresh.
- Use assertive announcements only when immediate action is required.
- Never announce every percentage tick or every incoming record.

14.5 Accessibility QA

For every critical route: automated axe checks, keyboard-only walkthrough, screen-reader smoke test, 200%/400% zoom, high-contrast/forced-colors check, reduced-motion check, and locale expansion. Include disabled, error, empty, loading, and offline states—not just the happy path.

15. Localization and international UX

15.1 Supported launch locales

English, Spanish, and French are first-class. All user-facing strings use translation keys. Content design begins from meaning and context, not string fragments.

15.2 Formatting

- Numbers, currency, percentages, and dates use locale-aware formatters.
- Day boundaries use merchant timezone; the UI displays it where ambiguity matters.
- Currency is always explicit when datasets or workspace context could differ.
- CSV examples respect common delimiter and decimal differences, but the parser never assumes locale alone proves meaning.
- Pluralization uses locale rules; never concatenate translated fragments.

15.3 Layout resilience

- Budget 30–40% text expansion for navigation and controls.
- Buttons grow before labels truncate. Icon-only fallbacks are not used for important actions.
- Tables may wrap headers to two lines; header tooltips are supplementary.
- Test real French and Spanish strings, accents, apostrophes, non-breaking spaces, and long error messages.

15.4 Language selection

The selector shows language names, not flags. Changing language does not reset the current task. Account preference persists after login; pre-login preference persists locally. Transactional messages use the recipient's preference at send time and include localized support paths.

15.5 Translation governance

- Every key includes context and screenshot/reference where ambiguity exists.
 - Native-language review covers critical journeys and marketing claims.
 - Missing-key telemetry records the key and route, never merchant data.
 - English fallback rate for Spanish/French screens must remain below the SDLC target.
-

16. Motion and interaction

Motion explains continuity; it does not decorate waiting.

Interaction	Duration	Behavior
Hover/focus surface	100–150 ms	Border/background transition
Drawer/sheet	180–220 ms	Fade + short translate
Widget placement	180–240 ms	Position interpolation with reserved target
Value changed live	≤1,200 ms	Background highlight that fades once
Toast	160 ms in/out	No spring/bounce
Landing mockup reveal	400–600 ms	One staggered entrance after content

Reduced motion removes transforms, parallax, animated chart drawing, and rearrangement interpolation. State changes remain visible through immediate styles and text.

17. Analytics and measurement plan

17.1 Event naming

Use `object_action` with stable schemas: `landing_cta_selected`, `demo_started`, `source_submitted`, `model_review_opened`, `model_confirmed`, `first_insight_viewed`, `widget_added`, `widget_render_changed`, `layout_saved`, `premium_boundary_viewed`, `checkout_started`.

Common safe properties:

- locale;
- route/template identifier;
- device class;
- plan code;
- source category, never filename;
- widget key, never merchant-configured title;
- render key;
- capability availability booleans;
- stage duration and standardized failure code;
- experiment and variant IDs.

Forbidden properties include raw values, source names, field names, customer information, entity names, user-entered dashboard names, and free-text support/search content.

Preview event boundary

The first landing revision emits `landing_cta_selected`, `demo_started`, and `model_review_opened` through a `JourneySink` interface. Its only implementation is a bounded, in-memory sink holding at most 100 events, with no network, cookies, persistent storage, or console logging. Runtime validation rejects unknown events, extra properties, and values outside the location/locale enums. Demo route visits are deduplicated across effect replay. Review events represent deliberate opening of the demo disclosure or re-entry to the detailed interpretation tab. The landing trust/source links emit CTA events with fixed `trust` and `sources` locations. Rendering content alone is not counted as reading it.

This establishes a testable event contract, not a production conversion baseline. A reviewed collector is still required for visitor measurement; provider, consent, retention, and access decisions remain pending. No lead capture is added in this checkpoint.

17.2 Experience KPIs

Area	Primary KPI	Diagnostic metrics
Landing	Qualified signup / meaningful demo	Hero CTA, section depth, demo completion, performance
Activation	First successful confirmed load	Source submit, review time, unresolved rate, failure/retry
Value	First insight viewed	Dashboard usable time, supported capabilities, inspect-data use
Habit	Second data arrival and weekly active workspace	Channel save, entry use, freshness, alert acknowledgement
Composition	Useful customization	Widget add/remove, render override, layout save failure
Premium	Activated capability after purchase	Boundary → checkout → activation → feature enabled
Trust	Corrective success	Model edits, reversals, duplicate skip, support escalation

17.3 Performance instrumentation

Track Core Web Vitals on marketing pages, route load, dashboard batch resolve, time to first usable canvas, per-widget render, cache status, and chart interaction latency. Segment by locale and connection class. The product target remains dashboard reads under 300 ms p95 and a usable repeat dashboard within eight seconds on throttled 3G.

18. Implementation architecture for the experience

18.1 Frontend route groups

```
apps/web/src/  
  marketing/      landing, pricing, use cases, resources  
  app-shell/      authenticated layout, navigation, command menu  
  dashboard/      canvas, picker, layout, widget frames  
  widgets/        render components keyed by widget manifests  
  ingestion/      add data, progress, review, results  
  channels/       channel detail, loads, guard decisions  
  entry/          quick, batch, corrections, offline queue  
  records/        tables, filters, entity evidence  
  alerts/         alert list and rules  
  settings/       account, workspace, plan, security  
  design-system/  tokens, primitives, patterns, charts  
  i18n/           locale resources and formatters  
  styles/         vanilla CSS tokens, reset, base, shared utilities
```

This is an organizational concept; final folder boundaries should follow the implemented repository conventions. Marketing pages and `/app` share tokens and primitives but load separate route bundles. Heavy dashboard/chart code must not inflate the landing-page entry bundle.

18.2 Vanilla CSS structure

Styling is authored in standards-based vanilla CSS. The frontend does not use Tailwind, Sass/Less, CSS-in-JS, CSS Modules, or a runtime styling library.

```
apps/web/src/styles/  
  tokens.css      semantic custom properties  
  reset.css       normalization and predictable defaults  
  base.css        document typography and element defaults  
  utilities.css   small, reviewed accessibility/layout helpers  
  
apps/web/src/design-system/  
  button/button.tsx  
  button/button.css  
  dialog/dialog.tsx  
  dialog/dialog.css  
  
apps/web/src/dashboard/  
  dashboard-canvas.tsx  
  dashboard-canvas.css
```

Declare the global order once with `@layer reset, base, components, utilities, overrides`. Component and feature files contribute to the appropriate layer. Use semantic custom properties from `tokens.css`, low-specificity locally namespaced classes, and `data-*` attributes for state and variants. Avoid IDs, deep descendant selectors, `!important`, and selectors that depend on incidental markup nesting.

Responsive behavior is mobile-first and content-driven. Media queries stay beside the component whose layout changes. Shared breakpoints may be represented as documented custom-media build constants only if the chosen browser/tooling baseline supports the approach without introducing a CSS preprocessor; otherwise repeat the reviewed media-query values explicitly.

Inline styles are limited to genuinely runtime-calculated geometry, such as a canvas position or measured chart dimension. Prefer setting a narrowly named CSS custom property from React and consuming it in the stylesheet. Focus, hover, disabled, validation, loading, reduced-motion, print, and locale-expansion behavior always belongs in CSS.

18.3 Design-system layers

1. **Tokens:** color, typography, space, radius, elevation, motion, breakpoints, z-index.
2. **Primitives:** Button, Link, Input, Select, Dialog, Drawer, Tooltip, Menu, Tabs, Table foundation.
3. **Patterns:** Page header, Filter bar, Data table, Empty state, Problem details, Upload progress, Entitlement card.
4. **Product components:** Widget frame, Widget picker card, Field interpretation row, Source preview, Channel status, Derived-state provenance.
5. **Templates:** Marketing section, Empty dashboard, Default canvas, Review workspace, Entry modes.

Avoid page-specific copies of primitives. New variants require a documented semantic need, not a visual preference.

18.4 Widget contract reflected in UI

Each widget manifest should provide or enable:

- stable widget key and localized question/title key;
- required semantic capabilities;
- allowed renders and default;
- configuration schema and defaults;
- minimum/preferred grid sizes;
- data contract/version;
- freshness and partial-data metadata;
- accessible summary data;
- entitlement and supported-state rules;
- cache policy on the backend, with render excluded where appropriate.

The frontend registry maps render keys to lazy-loaded renderers. Unknown widget or render versions fail inside the frame with a safe recovery path.

18.5 State ownership

- URL: restorable filters, dashboard ID, date range, selected tab.
- Server state: dashboards, widget data, uploads, records, alerts, entitlements; managed through TanStack Query and generated API types.
- Local persistent state: rail preference, dismissed education, safe recent commands, offline entry queue.

- Ephemeral state: open menus, hover/focus, in-progress drag.
- Optimistic state: entries and canvas arrangements only where rollback is explicit and visible.

18.6 Performance budgets

- Keep marketing initial JavaScript below 200 KB gzipped as required by the SDLC.
- Split authenticated route groups and widget renderers.
- Use one dashboard batch resolve request, then isolated refresh only where needed.
- Defer charts below the fold and avoid duplicate chart-library registrations.
- Reserve dimensions for mockups, charts, and skeletons to prevent layout shift.
- Use server/edge caching for public pages and ETags for eligible product reads.
- Audit the densest realistic canvas, not only a four-card demo.

18.7 Security and privacy in UI implementation

- Treat server authorization and entitlement responses as authoritative.
 - Never serialize access/refresh tokens into JavaScript-readable storage for the web client.
 - Sanitize exported/spreadsheet-bound values per the backend contract.
 - Prevent analytics, error reporting, and replay tools from capturing raw uploaded values or dashboard contents.
 - Use request IDs in supportable errors; do not expose stack traces.
 - Mask/restrict customer-related displays under the platform privacy model.
 - Make impersonation unmistakable in the separate admin surface with time limit and audit state.
-

19. Delivery sequence

Phase 1 — Foundations

- Finalize identity, tokens, typography licenses/assets, icon family, and component semantics.
- Build accessible primitives and Storybook/component documentation if adopted by the repository.
- Establish locale scaffolding and pseudo-localization.
- Create the marketing/app route split and performance measurement.
- Produce a consistent synthetic dataset for every screenshot, demo, and test.

Phase 2 — Landing and activation shell

- Implement navigation, hero, source ribbon, problem, how-it-works, three questions, trust, channels, canvas, global readiness, proof, comparison, pricing, FAQ, final CTA, footer.
- Build production-component mockups and optimized responsive assets.
- Implement sample workspace/demo and event taxonomy.
- Validate SEO metadata, structured data where accurate, consent, accessibility, localization, and initial weight.

Phase 3 — Core authenticated journey

- App shell and role-aware navigation.
- Empty dashboard and add-data sheet.
- Upload progress, data review, result summary.
- Starting canvas, batch resolution, widget states, live freshness.
- Records/evidence links and cursor-pagination patterns.

Phase 4 — Composition and daily work

- Arrange mode and keyboard alternative.
- Widget picker with real-data previews.
- Render/configuration switching and preferences.
- Multiple dashboards and templates.
- Channels, quick/batch/correction entry, offline queue, live updates.

Phase 5 — Conversion and hardening

- Contextual premium boundaries and post-purchase activation.
- Approved social proof and case study content.
- Native-language review, device/browser matrix, load/accessibility/security tests.

- Funnel analysis and controlled experiments.

Each phase remains subordinate to the SDLC's implementation phases and release gates; this sequence describes experience dependencies, not a competing project plan.

20. Acceptance checklist

Landing page

- [] The first viewport states audience, outcome, and primary action without relying on the mockup.
- [] Hero and section visuals use real Suq components with consistent synthetic data.
- [] Supported sources and the confirmation-before-commit behavior are explicit.
- [] The three product questions are prominent and match launch capabilities.
- [] Trust copy explains uncertainty, review, correction, and provenance plainly.
- [] Free/Premium differences match entitlements and retention behavior.
- [] No invented testimonial, logo, performance claim, integration, price, or policy appears.
- [] English, Spanish, and French layouts are reviewed.
- [] Keyboard, screen reader, zoom, contrast, and reduced motion pass.
- [] Initial page weight and Core Web Vitals meet the agreed budget.
- [] Events collect no merchant content.

Dashboard

- [] First data produces a useful supported-capability canvas automatically.
- [] Unsupported capabilities explain the missing concept rather than showing zero.
- [] Entire canvas resolves in one batch and widget failures remain isolated.
- [] Every widget has loading, refreshing, empty, partial, stale, error, locked, and ready behavior as applicable.
- [] Render switching is client-side when the data contract already supports it.
- [] Drag, resize, and reorder have keyboard/mobile alternatives and save-state feedback.
- [] Dates, currency, numbers, and day boundaries follow locale/timezone.
- [] Free-tier advertising is clearly labeled, limited, contextual, and leaves no gap when absent.
- [] Mobile order follows explicit reading order.
- [] Dense, realistic canvas performance meets the SDLC target.

Data-heavy surfaces

- [] Tables use cursor-aware Previous/Next or Load more, never fictional numbered pages.
- [] Sort/filter changes reset cursor and remain restorable through URL/state.
- [] Sticky headers, long values, row actions, density, selection scope, empty states, and mobile adaptation are defined.
- [] Export is an asynchronous job and not a client-side pagination loop.
- [] Error states preserve existing data and expose safe retry plus request ID.

Ingestion and trust

- [] Review displays type, meaning, confidence/evidence, sample values, and supported analyses.
 - [] Low-confidence visual cells can be compared with source crops.
 - [] Changes re-render a real preview.
 - [] Consequences are summarized before confirm, remodel, intent change, or load reversal.
 - [] Result summary distinguishes loaded, duplicate, rejected, and reversed records.
 - [] Raw/unmapped data preservation is explained where relevant.
-

21. SDLC traceability

Concept area	Primary SDLC requirements / sections
Authentication and role-aware surfaces	FR-A-1-FR-A-5
Source choice, progress, review, correction, result	FR-U-1-FR-U-12
Channels, intent, fill, any input	FR-C-1-FR-C-5
Quick/batch/correction and offline entry	FR-E-1-FR-E-6
Derived-state display and provenance	FR-S-1-FR-S-4
Guard decisions and load reversal	FR-G-1-FR-G-6
Canvas, widgets, renders, templates, mobile, failures	FR-D-1-FR-D-13
Alerts and premium channels	FR-AL requirements; FR-P-2-FR-P-4
Premium surfaces and downgrade behavior	FR-P-1-FR-P-11
Contextual sponsored widget	FR-AD requirements; FR-D-13; FR-P-8
Latency, accessibility, localization, page weight	NFR-1, NFR-5, NFR-6, NFR-10
Navigation, onboarding, upsell, canvas wireframe	SDLC §6.13
Widget catalog	SDLC Appendix A
Testing and release readiness	SDLC chapters 8-12

22. Content and design dependencies

Decisions required before final visual design ships:

- Approved logo/wordmark and whether “Suq” needs a pronunciation or meaning note in target markets.
- Verified price, billing interval, tax presentation, trial/card policy, and regional payment availability.
- Supported launch countries and any source-format or SMS limitations by country.
- Public security/privacy claims approved by legal and engineering.
- Consent and evidence for testimonials, logos, and case studies.
- Final synthetic demo dataset with internally consistent values across three locales.
- Font files, licensing, fallback metrics, and performance cost.
- Screenshot production workflow so marketing mockups track production components.
- Analytics/consent vendor and privacy-safe event review.

Until these are resolved, use clearly labeled placeholders in design files and never publish assumptions as promises.

References

- [Suq Insights SDLC v3.0](#) — canonical product and engineering specification.
- [Milestone Webflow template](#) — landing-page visual and section inspiration.
- [Milestone template overview](#) — source description and preview.
- [E-commerce Management Dashboard](#) — authenticated dashboard layout inspiration.
- [Triple Whale](#) — ecommerce outcome messaging and product-led presentation reference.
- [Polar Analytics](#) — goal-based commerce analytics and demo framing reference.

Document owner: Product/design · **Implementation authority:** [SDLC.md](#) v3.0 · **Review cadence:** at each material experience checkpoint and before beta.

Accepted amendment: Cinematic Suq (2026-09-05)

The owner approved one continuous merchant story across the landing page and fictional demo. This amendment supersedes the separate Daily decisions / How it works / Trust presentation above, while preserving the finalized PR #8 hero, plans, FAQ, and closing action.

Three chapters — Understand the day, Inspect the evidence, Try the next sale — share one typed, browser-memory scenario above the routes. Source selection, illustrative role review/confirmation, customer-evidence availability, dashboard selections, and the reversible sample sale survive navigation and language changes. Reset sample restores defaults; a refresh starts fresh. This is demonstration state, not merchant persistence or analytics.

Role review applies only to the original illustrative source records. It does not reprocess the historical dashboard. The next sale changes only the separately identified stock after the historical cutoff (12 → 11); historical money, chart observations, and risk estimates remain unchanged. Missing customer evidence makes customer analyses unavailable, never zero. Source or role changes invalidate review confirmation; repeated confirmation cannot record extra sales.

Desktop uses scrolling copy beside one sticky scene with explicit chapter controls. IntersectionObserver changes presentation only. Mobile, short viewports, enlarged content, and unsupported observers retain sequential scenes without duplicated controls. CSS provides restrained transitions with immediate reduced-motion states. Keyboard focus must never be hidden by automatic chapter changes.

Delivery: three successive, unmerged PRs against dev, in order: scenario continuity, cinematic presentation, final accessibility/performance evidence. Each includes its predecessor until earlier PRs merge. Public support/legal destinations, real analytics, authenticated onboarding, and application workflows remain separate pending work.

Acceptance: SDLC §1.2, FR-U-4/5/12, FR-G-6, FR-E-1, FR-D-12 and NFR-5/6/9/10, as illustrative marketing behavior only. Validate continuity, invalidation, cancel/undo/reset, repeated actions, Back/direct links, all locales, scroll isolation, historical integrity, keyboard/forced colors/reduced

motion, mobile and short viewports, 200% text, browser accessibility, and initial JavaScript below 200 KB gzip. Capture screenshots and an interaction recording; no conversion claim without merchant evidence.

Cinematic presentation checkpoint

The landing narrative now uses three connected chapters. The first scene has compact Sales / Stock / Customers question controls, the second reuses the original-record review, and the third reuses the preview/confirm/undo sale. Plans, FAQ, closing action and the immediate hero briefing remain below/above the story as approved. The legacy separate trust and workflow sections are removed.

With sufficient width and height, chapter copy scrolls beside one visible sticky product scene. Inactive scenes are inert and excluded from the accessibility tree during crossfades. Scroll observes chapter intersections and changes presentation only; it cannot hide a scene containing keyboard focus. Explicit chapter buttons remain available. Without IntersectionObserver, on mobile/short screens, or with enlarged text, copy and scenes remain sequential in the same DOM order with no duplicated controls.

Validation at this checkpoint: 74 web tests, including scroll/state isolation, focus protection and locale continuity; Chromium EN/ES/FR chapter controls, scroll selection, mobile/short fallback and axe including contrast. The final delivery adds the full viewport matrix, recording and performance evidence.

First cinematic functional evidence

The first fictional landing/demo delivery supplied the shared scenario and functional interaction scope; the subsequent owner review requested stronger art direction. Review/stock confirmation is guarded against accidental double clicks and held-key repeats. The dashboard labels stock after the historical cutoff separately from immutable historical figures. Programmatic route focus and direct demo disclosures remain functional. The final browser review corrected system-color contrast in the closing invitation and selected metrics, and made header navigation wrap under French text expansion.

Validation: 78 web tests, 27 Chromium continuity/layout cases across EN/ES/FR, browser axe including contrast, and a 122.9 KB initial JavaScript gzip build below 200 KB. Screenshots, a short interaction recording, reproduction commands and limitations are in [docs/reviews/cinematic-experience.md](#). Physical assistive-technology, native-speaker and merchant-outcome reviews remain human follow-up. This evidence supports the fictional demonstration only; it neither establishes conversion improvement nor completes the production SaaS phase gates.

Art-direction revision: the story leads (2026-09-06)

Owner feedback: the first cinematic implementation felt shallow and its mockups did not look real. The owner selected a more theatrical brand story, with dramatic scene changes and visual storytelling supported by the product demonstration. Functional test results from the first delivery did not establish the quality of its art direction.

The revised sequence uses three distinct compositions:

1. **The shop is busy. What is moving it?** Large editorial typography and a 312-transaction motif establish the scale of the fictional trading day. A compact workspace shows the actual sample product comparisons, stock arithmetic, or customer-history visualization. The chart uses existing aggregates, not invented transaction rows.
2. **A small detail. A different story.** The desktop environment cuts to ink and lime. Original CSV rows sit beside the role selector and confirmation, bringing the meaning of one column into focus. The source review remains illustrative; it does not reprocess history.
3. **The next sale. Now you see it.** Mint marks the shift to action. An inventory balance and movement ledger sit beside quick entry. The twelfth unit is marked as a draft during preview, leaves only after confirmation, and returns on undo. The historical balance stays at 12.

The scene surfaces use consistent workspace identity, date, readable data, and functioning controls. Large typography and changes in scene scale provide the theatrical material; fabricated browser chrome, unavailable application navigation, videos, and new animation dependencies are unnecessary. Background lighting cuts immediately to keep text contrast stable; CSS crossfades and restrained movement apply to presentation only. Reduced motion removes those transitions.

The immediate hero briefing, plan comparison, FAQ and closing invitation retain their existing place. Mobile, short and enlarged-text layouts remain sequential. A scene that grows beyond the available desktop viewport also falls back to normal flow, so expanded evidence and translated controls remain reachable. Missing customer identifiers remove the customer visualization and show the existing explanation.

Acceptance stays within the earlier fictional marketing scope and requirement IDs. Review the revised screenshots and recording for the strength of the art direction; automated accessibility and behavior checks cannot establish immersion or conversion. Existing cinematic PRs stay unmerged. This revision follows their shared-state and accessibility work.

Revision validation: 79 web tests, 30 Chromium continuity/layout cases across EN/ES/FR with axe including contrast, and a 125.3 KB initial JavaScript gzip build. See [docs/reviews/cinematic-experience.md](#) for the revised scenes, interaction recording, reproduction instructions and remaining human review limits.

Desktop workstation amendment (2026-09-06)

The owner requested stronger immersion and mockups that visibly sit inside a desktop display. The story now invites the visitor to take a seat at Mercado Norte: see the trading day on screen, inspect the evidence, and make the next move in the same sample workspace.

The product demonstration is framed as a desktop monitor, with a slim dark bezel, camera detail, decorative window title bar, lower edge and metal stand. The wider stage and consistent minimum screen height keep the monitor visually grounded between chapters. The large floating numerical motifs are removed so the physical workstation becomes the focal point. Paper, ink and mint still mark the narrative changes; the old zoom movement is removed.

The screen contains actual React components and shared scenario controls, not a screenshot. Decorative window marks and hardware are hidden from assistive technology and are not clickable. No fake address, connection status or operating-system action is introduced. This owner-requested frame supersedes the previous amendment's choice to omit window chrome.

On mobile, the monitor becomes a slim window frame; the camera, lower edge and stand are omitted. Text is never scaled down to fit the hardware. Enlarged or expanded content still falls back to normal page flow, and the shared dropdown renders above the frame. System colors simplify the hardware; reduced-motion users receive immediate scene changes. Shadows are limited to the physical display and stand, leaving section backgrounds flat.

The demonstration's confirmation, undo, historical-cutoff and missing-customer-evidence rules are unchanged. This is a visual revision of PR #12, not a new product capability or a claim of measured conversion improvement.

Inline merchant story amendment (2026-09-12)

The merchant story stays within the landing page. The optional full-screen experience, its entry and exit actions, modal dialog, and page scroll lock have been removed at the owner's request. Chapter navigation, "Follow the evidence" and "Continue to the next sale" operate on the inline story. Desktop retains its responsive sticky presentation; mobile, short screens and enlarged text retain sequential scenes. Review confirmation, sample-sale preview/confirm/undo, language continuity and keyboard focus behavior remain required.